SHIVANSH / ONGC BRRP | PRELIMINARY DESIGN DEVELOPMENT

DRAWING REGISTER AND ENGINEERING STATUS

P4 - FOR ENGINEERING REVIEW | CONSTRUCTION RELEASE DEFERRED | NOT FOR PROCUREMENT OR EXECUTION

PACKAGE PURPOSE

Develop existing bridge concepts into a traceable preliminary engineering package.

Use confirmed criteria and source drawings without inventing unverified site or fabrication dimensions.

Three arrangement sheets + three bearing/interface sheets + three detailing schedules.

Six original tender landing sheets are appended unchanged after the development sheets.

Open engineering inputs and calculations are recorded in the companion report and workbook.

Proposed ID	Bridge	Sheet scope	Status
SHV-BRRP-101-GA-P4	ICW-ICG LD	Study-source arrangement	PRELIMINARY
SHV-BRRP-102-GA-P4	ICP-ICG LD	Study-source arrangement	PRELIMINARY
SHV-BRRP-103-GA-P4	BHS-SLQ LD	Study-source arrangement	PRELIMINARY
SHV-BRRP-101-BI-P4	ICW-ICG LD	Bearing / landing interface	PRELIMINARY
SHV-BRRP-102-BI-P4	ICP-ICG LD	Bearing / landing interface	PRELIMINARY
SHV-BRRP-103-BI-P4	BHS-SLQ LD	Bearing / landing interface	PRELIMINARY
SHV-BRRP-101-DD-P4	ICW-ICG LD	Detail development schedule	PRELIMINARY
SHV-BRRP-102-DD-P4	ICP-ICG LD	Detail development schedule	PRELIMINARY
SHV-BRRP-103-DD-P4	BHS-SLQ LD	Detail development schedule	PRELIMINARY

COMPUTATION BOUNDARY

Computed: loading arithmetic, source deflection ratios, thermal sensitivity, section geometry and ideal wrap quantities.

Not computed: a new global structural model, code member resistances, connection/bearing capacities or marine-operation design.

The detailed drawing register identifies the calculations and measurements required to close each detail.

SHV-BRRP-P4-INDEX | Rev P4 | 25 Oct 2026 | Source-based development sheet; new Shivansh ID

Basis: DC3.4 PartI Rev14 / BRRP PartII / B774 scope, addendum and tender sources


No member resistance, connection, bearing or lift approval is implied. Source results are not a new independently solved analysis.

SHIVANSH / ONGC BRRP | PRELIMINARY DESIGN DEVELOPMENT


ICW-ICG LD - PRELIMINARY ARRANGEMENT

P4 - FOR ENGINEERING REVIEW | CONSTRUCTION RELEASE DEFERRED | NOT FOR PROCUREMENT OR EXECUTION

SOURCE-STUDY THREE-DIMENSIONAL MODEL



SOURCE CROSS-SECTION



Structural depth / overall width: not verified

Loading-width reference: 1.2 m

LONGITUDINAL STUDY REFERENCE - NOT TO SCALE

Study model length 56 m; approximate reported gap 54.5 m

ICW - sliding

ICG - hinged/fixed intent

Final bearing centres, levels, skew, member coordinates, section mapping and camber profile require engineering verification.

25-year design life. E=210000 MPa; density=7850 kg/m3; alpha=12x10^-6 /C. (Criteria pp66,119)

Global walkway loading2.4525kN/m2; local grating loading4.905kN/m2. Actual loading areas must be reconciled.

Study source vertical deflection 105mm / criteria limit 140mm; lateral 87mm / 112mm.

Wind gust duration: 15sec per Annexure5. Speed and elevation correction require documented calculation.

Camber to compensate verified dead-load deflection; source1:200 statement is not adopted.

Include approved landing modifications and applicable ICG/ICP jacket strengthening.

SHV-BRRP-101-GA-P4 | Rev P4 | 25 Oct 2026 | Source-based development sheet; new Shivansh ID

Source B774-000-83-43-BPR-0004 Rev0; combined SOW/report PDF pp.133-135;152-153


No member resistance, connection, bearing or lift approval is implied. Source results are not a new independently solved analysis.

SHIVANSH / ONGC BRRP | PRELIMINARY DESIGN DEVELOPMENT


ICP-ICG LD - PRELIMINARY ARRANGEMENT

P4 - FOR ENGINEERING REVIEW | CONSTRUCTION RELEASE DEFERRED | NOT FOR PROCUREMENT OR EXECUTION

SOURCE-STUDY THREE-DIMENSIONAL MODEL



SOURCE CROSS-SECTION



Structural depth / overall width: not verified

Loading-width reference: 1.2 m

LONGITUDINAL STUDY REFERENCE - NOT TO SCALE

Study model length 84 m; approximate reported gap 80.5 m

ICP - sliding

ICG - hinged/fixed intent

Final bearing centres, levels, skew, member coordinates, section mapping and camber profile require engineering verification.

25-year design life. E=210000 MPa; density=7850 kg/m3; alpha=12x10^-6 /C. (Criteria pp66,119)

Global walkway loading2.4525kN/m2; local grating loading4.905kN/m2. Actual loading areas must be reconciled.

Study source vertical deflection 177mm / criteria limit 210mm; lateral 123mm / 168mm.

Wind gust duration: 15sec per Annexure5. Speed and elevation correction require documented calculation.

Camber to compensate verified dead-load deflection; source1:200 statement is not adopted.

Include approved landing modifications and applicable ICG/ICP jacket strengthening.

SHV-BRRP-102-GA-P4 | Rev P4 | 25 Oct 2026 | Source-based development sheet; new Shivansh ID

Source B774-000-83-43-BPR-0003 Rev0; combined SOW/report PDF pp.196-199;207-209


No member resistance, connection, bearing or lift approval is implied. Source results are not a new independently solved analysis.

SHIVANSH / ONGC BRRP | PRELIMINARY DESIGN DEVELOPMENT


BHS-SLQ LD - PRELIMINARY ARRANGEMENT

P4 - FOR ENGINEERING REVIEW | CONSTRUCTION RELEASE DEFERRED | NOT FOR PROCUREMENT OR EXECUTION

SOURCE-STUDY THREE-DIMENSIONAL MODEL



SOURCE CROSS-SECTION



Structural depth / overall width: not verified

Loading-width reference: 2.324 m

LONGITUDINAL STUDY REFERENCE - NOT TO SCALE

Study model length 42 m; approximate reported gap 40 m

BHS - sliding

SLQ - hinged/fixed intent

Final bearing centres, levels, skew, member coordinates, section mapping and camber profile require engineering verification.

25-year design life. E=210000 MPa; density=7850 kg/m3; alpha=12x10^-6 /C. (Criteria pp66,119)

Global walkway loading2.4525kN/m2; local grating loading4.905kN/m2. Actual loading areas must be reconciled.

Study source vertical deflection 32mm / criteria limit 105mm; lateral 76mm / 84mm.

Wind gust duration: 3sec per Annexure5. Speed and elevation correction require documented calculation.

Camber to compensate verified dead-load deflection; source1:200 statement is not adopted.

BHS new bridge and services must be accepted before existing bridge demolition.

SHV-BRRP-103-GA-P4 | Rev P4 | 25 Oct 2026 | Source-based development sheet; new Shivansh ID

Source B774-000-83-43-BPR-0005 RevA; combined SOW/report PDF pp.97-100;122-123

No member resistance, connection, bearing or lift approval is implied. Source results are not a new independently solved analysis.


SHIVANSH / ONGC BRRP | PRELIMINARY DESIGN DEVELOPMENT

ICW-ICG LD - BEARING AND LANDING INTERFACE DEVELOPMENT

P4 - FOR ENGINEERING REVIEW | CONSTRUCTION RELEASE DEFERRED | NOT FOR PROCUREMENT OR EXECUTION

FUNCTIONAL SUPPORT DIAGRAM - COMPONENTS NOT SIZED OR SELECTED


ICW PLATFORM | SLIDING



Longitudinal movement + lateral/vertical guides

ICG PLATFORM | HINGED / PINNED INTENT

Axial thrust and rotation provision to be designed



Does not imply moment-rigid frame-end restraint

MOVEMENT AND FORCE DESIGN BASIS

Required directional translation =1.5 x (absolute platform-A translation + absolute platform-B translation).

Required hinged-connection axial action =1.5 x expected axial thrust, with appropriate signed action envelope.

Thermal sensitivity deltaL =alpha x L x deltaT; compatible combined movement must avoid double counting.

Thermal sensitivity for this study length = 0.672 mm per degree C; actual design temperature range remains to be set.

Criteria location-tolerance wording must be interpreted for existing supports; it is not an adopted bearing-travel value.

DETAILS TO CLOSE BEFORE COMPONENT SIZING

Coordinates and datum; rotations; signed concurrent reactions; uplift and friction; travel and guide gaps.

Bearing pressure/contact; local plates and stiffeners; anchorage/connection resistance; corrosion and inspection access.

Surveyed existing steel / UT condition; landing/deck/jacket capacity; installation tolerances and replacement method.

Use correct platform drawing and verify member/interface labels before detailed modelling.

SHV-BRRP-101-BI-P4 | Rev P4 | 25 Oct 2026 | Source-based development sheet; new Shivansh ID

DC3.4 PartI3.4.16.4.17 pp42-43; source arrangement and platform drawings; dimensions pending

No member resistance, connection, bearing or lift approval is implied. Source results are not a new independently solved analysis.


SHIVANSH / ONGC BRRP | PRELIMINARY DESIGN DEVELOPMENT

ICP-ICG LD - BEARING AND LANDING INTERFACE DEVELOPMENT

P4 - FOR ENGINEERING REVIEW | CONSTRUCTION RELEASE DEFERRED | NOT FOR PROCUREMENT OR EXECUTION

FUNCTIONAL SUPPORT DIAGRAM - COMPONENTS NOT SIZED OR SELECTED


ICP PLATFORM | SLIDING



Longitudinal movement + lateral/vertical guides

ICG PLATFORM | HINGED / PINNED INTENT

Axial thrust and rotation provision to be designed



Does not imply moment-rigid frame-end restraint

MOVEMENT AND FORCE DESIGN BASIS

Required directional translation =1.5 x (absolute platform-A translation + absolute platform-B translation).

Required hinged-connection axial action =1.5 x expected axial thrust, with appropriate signed action envelope.

Thermal sensitivity deltaL =alpha x L x deltaT; compatible combined movement must avoid double counting.

Thermal sensitivity for this study length = 1.008 mm per degree C; actual design temperature range remains to be set.

Criteria location-tolerance wording must be interpreted for existing supports; it is not an adopted bearing-travel value.

DETAILS TO CLOSE BEFORE COMPONENT SIZING

Coordinates and datum; rotations; signed concurrent reactions; uplift and friction; travel and guide gaps.

Bearing pressure/contact; local plates and stiffeners; anchorage/connection resistance; corrosion and inspection access.

Surveyed existing steel / UT condition; landing/deck/jacket capacity; installation tolerances and replacement method.

Use correct platform drawing and verify member/interface labels before detailed modelling.

SHV-BRRP-102-BI-P4 | Rev P4 | 25 Oct 2026 | Source-based development sheet; new Shivansh ID

DC3.4 PartI3.4.16.4.17 pp42-43; source arrangement and platform drawings; dimensions pending

No member resistance, connection, bearing or lift approval is implied. Source results are not a new independently solved analysis.


SHIVANSH / ONGC BRRP | PRELIMINARY DESIGN DEVELOPMENT

BHS-SLQ LD - BEARING AND LANDING INTERFACE DEVELOPMENT

P4 - FOR ENGINEERING REVIEW | CONSTRUCTION RELEASE DEFERRED | NOT FOR PROCUREMENT OR EXECUTION

FUNCTIONAL SUPPORT DIAGRAM - COMPONENTS NOT SIZED OR SELECTED


BHS PLATFORM | SLIDING



Longitudinal movement + lateral/vertical guides

SLQ PLATFORM | HINGED / PINNED INTENT

Axial thrust and rotation provision to be designed



Does not imply moment-rigid frame-end restraint

MOVEMENT AND FORCE DESIGN BASIS

Required directional translation =1.5 x (absolute platform-A translation + absolute platform-B translation).

Required hinged-connection axial action =1.5 x expected axial thrust, with appropriate signed action envelope.

Thermal sensitivity deltaL =alpha x L x deltaT; compatible combined movement must avoid double counting.

Thermal sensitivity for this study length = 0.504 mm per degree C; actual design temperature range remains to be set.

Criteria location-tolerance wording must be interpreted for existing supports; it is not an adopted bearing-travel value.

DETAILS TO CLOSE BEFORE COMPONENT SIZING

Coordinates and datum; rotations; signed concurrent reactions; uplift and friction; travel and guide gaps.

Bearing pressure/contact; local plates and stiffeners; anchorage/connection resistance; corrosion and inspection access.

Surveyed existing steel / UT condition; landing/deck/jacket capacity; installation tolerances and replacement method.

SLQ conflict remains a query: report/methodology fixed intent versus contradictory SOW wording.

SHV-BRRP-103-BI-P4 | Rev P4 | 25 Oct 2026 | Source-based development sheet; new Shivansh ID

DC3.4 PartI3.4.16.4.17 pp42-43; source arrangement and platform drawings; dimensions pending

No member resistance, connection, bearing or lift approval is implied. Source results are not a new independently solved analysis.

SHIVANSH / ONGC BRRP | PRELIMINARY DESIGN DEVELOPMENT

ICW-ICG LD - DETAILING AND CALCULATION INTERFACE SCHEDULE

P4 - FOR ENGINEERING REVIEW | CONSTRUCTION RELEASE DEFERRED | NOT FOR PROCUREMENT OR EXECUTION

PROPOSED DETAIL MARKS - ASSIGN TO FINAL MODEL AND CALCULATIONS BEFORE DRAWING RELEASE

Mark	Detail family	Calculation / evidence required	Current status
CH	Chords	Section/group mapping; axial/bending/buckling/fatigue	NOT SELECTED
BR	Braces / crossframes	Node geometry; effective lengths; joint capacity	NOT SELECTED
WB	Walkway beams	Actual spans; local loading; grating support	NOT SELECTED
EC	End connection	Concurrent forces; rotations; local resistance	NOT SIZED
BE	Bearing / guides	Movement; pressure; uplift; friction; anchorage	NOT SIZED
LS	Landing / stool	Survey/UT; support reactions; existing capacity	VERIFY SOURCE
SS	Services supports	Routing; operational/hydrotest loads; future allowance	COORDINATE
AC	Access / fittings	Clear width; handrails; grating; standards/IRT	SOURCE DETAILS
TW	Temporary works	Stage loads; support arrangement; stability	NOT DESIGNED
LP	Lifting interface	Verified mass/COG; rigging; skew/dynamics	NOT DESIGNED
SF	Transport restraints	Vessel motions; support reactions; deck checks	NOT DESIGNED

INSPECTION AND DOCUMENT REQUIREMENTS

Material traceability and certificates; approved welding procedures / qualifications; dimensional control.

NDT extent, hold/witness points and acceptance per applicable specification and approved inspection plan.

Coating exposure/system and inspection; source MTO IRT pp15-34; no generic welding or NDT percentage assumed.

Every final dimension/detail must identify controlling source, calculation reference, revision and engineering reviewer.

BRIDGE-SPECIFIC INTERFACE

IC complex: landing drawing references, addendum jacket strengthening, access and adjacent live-service clearance.

SHIVANSH / ONGC BRRP | PRELIMINARY DESIGN DEVELOPMENT

ICP-ICG LD - DETAILING AND CALCULATION INTERFACE SCHEDULE

P4 - FOR ENGINEERING REVIEW | CONSTRUCTION RELEASE DEFERRED | NOT FOR PROCUREMENT OR EXECUTION

PROPOSED DETAIL MARKS - ASSIGN TO FINAL MODEL AND CALCULATIONS BEFORE DRAWING RELEASE

Mark	Detail family	Calculation / evidence required	Current status
CH	Chords	Section/group mapping; axial/bending/buckling/fatigue	NOT SELECTED
BR	Braces / crossframes	Node geometry; effective lengths; joint capacity	NOT SELECTED
WB	Walkway beams	Actual spans; local loading; grating support	NOT SELECTED
EC	End connection	Concurrent forces; rotations; local resistance	NOT SIZED
BE	Bearing / guides	Movement; pressure; uplift; friction; anchorage	NOT SIZED
LS	Landing / stool	Survey/UT; support reactions; existing capacity	VERIFY SOURCE
SS	Services supports	Routing; operational/hydrotest loads; future allowance	COORDINATE
AC	Access / fittings	Clear width; handrails; grating; standards/IRT	SOURCE DETAILS
TW	Temporary works	Stage loads; support arrangement; stability	NOT DESIGNED
LP	Lifting interface	Verified mass/COG; rigging; skew/dynamics	NOT DESIGNED
SF	Transport restraints	Vessel motions; support reactions; deck checks	NOT DESIGNED

INSPECTION AND DOCUMENT REQUIREMENTS

Material traceability and certificates; approved welding procedures / qualifications; dimensional control.

NDT extent, hold/witness points and acceptance per applicable specification and approved inspection plan.

Coating exposure/system and inspection; source MTO IRT pp15-34; no generic welding or NDT percentage assumed.

Every final dimension/detail must identify controlling source, calculation reference, revision and engineering reviewer.

BRIDGE-SPECIFIC INTERFACE

IC complex: landing drawing references, addendum jacket strengthening, access and adjacent live-service clearance.

SHIVANSH / ONGC BRRP | PRELIMINARY DESIGN DEVELOPMENT

BHS-SLQ LD - DETAILING AND CALCULATION INTERFACE SCHEDULE

P4 - FOR ENGINEERING REVIEW | CONSTRUCTION RELEASE DEFERRED | NOT FOR PROCUREMENT OR EXECUTION

PROPOSED DETAIL MARKS - ASSIGN TO FINAL MODEL AND CALCULATIONS BEFORE DRAWING RELEASE

Mark	Detail family	Calculation / evidence required	Current status
CH	Chords	Section/group mapping; axial/bending/buckling/fatigue	NOT SELECTED
BR	Braces / crossframes	Node geometry; effective lengths; joint capacity	NOT SELECTED
WB	Walkway beams	Actual spans; local loading; grating support	NOT SELECTED
EC	End connection	Concurrent forces; rotations; local resistance	NOT SIZED
BE	Bearing / guides	Movement; pressure; uplift; friction; anchorage	NOT SIZED
LS	Landing / stool	Survey/UT; support reactions; existing capacity	VERIFY SOURCE
SS	Services supports	Routing; operational/hydrotest loads; future allowance	COORDINATE
AC	Access / fittings	Clear width; handrails; grating; standards/IRT	SOURCE DETAILS
TW	Temporary works	Stage loads; support arrangement; stability	NOT DESIGNED
LP	Lifting interface	Verified mass/COG; rigging; skew/dynamics	NOT DESIGNED
SF	Transport restraints	Vessel motions; support reactions; deck checks	NOT DESIGNED

INSPECTION AND DOCUMENT REQUIREMENTS

Material traceability and certificates; approved welding procedures / qualifications; dimensional control.

NDT extent, hold/witness points and acceptance per applicable specification and approved inspection plan.


Coating exposure/system and inspection; source MTO IRT pp15-34; no generic welding or NDT percentage assumed.

Every final dimension/detail must identify controlling source, calculation reference, revision and engineering reviewer.


BRIDGE-SPECIFIC INTERFACE

BHS: piping/cable supports, roofing, service transfer, lifeboat/muster interfaces and demolition package.


B774-101-83-43-0002



PLAN AT EL(+)18.300 (T.O.S.)



PLAN AT LQ LEVEL AT BRIDGE LANDING AREA EL(+)27.750 (T.O.S.)



PART ELEVATION OF ROW B


REF. DWG. NO.	REFERENCE DRAWING TITLE
ICW-70-050 TO ICW-70-059	ICW PLATFORM DECK DRWAINGS

NOTES :-


1. DO NOT SCALE THE DRAWING, WORK TO DIMENSIONS ONLY.
2. ALL DIMENSIONS ARE IN MM AND LEVELS ARE IN M U.N.O.
3. ALL ELEVATIONS ARE W.R.T. CHART DATUM (CD) 0.0M CHART DATUM FOR INDIAN WATERS SHALL BE 2.5M BELOW MEAN SEA LEVEL (MSL).
4. MATERIAL SPECIFICATIONS
   a) ALL STIFFENERS, FLANGE EXTENSION PLATES ETC. SHALL BE OF SAME / HIGHER GRADE AS ELEMENT TO WHICH THEY ARE CONNECTED U.N.O.
5. MATERIAL TYPES LISTED IN SC NOS SHALL CONFORM TO ONGC SPEC 6001 F.
6. FABRICATOR TO ENSURE MIN 75MM CLEAR GAP B/W HE WELDS FOR CROSS BRACES AND CROSS JOINTS.
7. ALL WELDS SHALL BE FULL PENETRATION WELDS.
8. FOR GRATING REFER EIL STD. 7-60-0802.
9. FOR HANDRAIL REFER EIL STD. 7-60-0801.

- ALL DETAILS, DIMENSIONS, LEVELS & MEMBER SIZES IN THE DRAWING ARE INDICATIVE AND ARE PROVIDED FOR BIDDERS UNDERSTANDING OF SCOPE OF WORK ONLY.ALL DETAILS SHOWN IN THE DRAWING SHALL BE VERIFIED BY CONTRACTOR DURING PRE-ENGINEERING SURVEY & DETAIL ENGINEERING SHALL BE CARRIED OUT BY CONTRACTOR FOR EXECUTION OF WORKS.
- ALL THE DIMENSIONS ARE IN MM AND LEVELS ARE IN METER (U.N.O.)


ISSUED FOR TENDER




SECTION 3-3




SECTION 4-4




SECTION 5-5




SECTION 6-6




SECTION 7-7




SECTION 8-8




SECTION 9-9



SECTION 1-1



SECTION 2-2



SECTION 3-3

REV.	DATE	REVISIONS	BY	CHKD	APPD	PEMPC
A	01.12.25	ISSUED FOR TENDER	MUNISH	AMS	DP	

इंजीनियर्स इंडिया लिमिटेड ENGINEERS INDIA LIMITED (A Govt. of India Undertaking)

ऑयल एण्ड नेचुरल गैस कारपोरेशन लिमिटेड
OIL AND NATURAL GAS CORPORATION LIMITED

REFURBISHMENT/REPLACEMENT OF BRIDGES IN MH ASSET


STRENGTHENING OF ICW UPPER DECK

SCALE	JOB NO.	UNIT	DIVN.	DEPT.	DWG. NO.	REV.
1:100	B774	101	83	43	0002	A


प्रस्तुत आरेख एवं इसमें निहित डिजाइन इंजीनियर्स इंडिया लिमिटेड की संपत्ति है। ये मात्र उधार दिए गए है और इसको किसी अन्य प्रयोग हेतु जाएंगे और न ही संपत्ति और किसी प्रयोग के अलावा इसका कार्य अन्य प्रयोग हेतु जाएंगे और न ही संपत्ति और किसी प्रयोग उधार देने वाले द्वारा उधारकर्ता को लिखित रूप से दी गई सहमति से होगा।
The drawing, design and details given on this format are the property of ENGINEERS INDIA LIMITED. They are merely loaned on the borrower's express agreement that they will not be reproduced, copied, exhibited or used, except in the limited way permitted by a written consent given by the lender to the borrower for the intended use.

3-1641-0501 REV.2 A1-841x594


B774-101-83-43-0003




PART PLAN OF MAIN DECK AT EL(+)26.500 (T.O.S.)




PART ELEVATION OF ROW B




PART ELEVATION OF ROW 2




SECTION 1–1




SECTION 2–2




SECTION 3–3




SECTION 4–4




SECTION 5–5



SECTION 6–6



SECTION 7–7



SECTION 8–8

REF. DWG. NO.	REFERENCE DRAWING TITLE
ICW-70-050 TO ICW-70-059	ICW PLATFORM DECK DRWAINGS

NOTES :-

1. DO NOT SCALE THE DRAWING, WORK TO DIMENSIONS ONLY.
2. ALL DIMENSIONS ARE IN MM AND LEVELS ARE IN M U.N.O.
3. ALL ELEVATIONS ARE W.R.T. CHART DATUM (CD) 0.0M CHART DATUM FOR INDIAN WATERS SHALL BE 2.5M BELOW MEAN SEA LEVEL (MSL).
4. MATERIAL SPECIFICATIONS
   a) ALL STIFFENERS, FLANGE EXTENSION PLATES ETC. SHALL BE OF SAME / HIGHER GRADE AS ELEMENT TO WHICH THEY ARE CONNECTED U.N.O.
5. MATERIAL TYPES LISTED IN SC NOS SHALL CONFORM TO ONGC SPEC 6001 F.
6. FABRICATOR TO ENSURE MIN 75MM CLEAR GAP B/W HE WELDS FOR CROSS BRACES AND CROSS JOINTS.
7. ALL WELDS SHALL BE FULL PENETRATION WELDS.
8. FOR GRATING REFER EIL STD. 7–60–0802.
9. FOR HANDRAIL REFER EIL STD. 7–60–0801.

* ALL DETAILS, DIMENSIONS, LEVELS & MEMBER SIZES IN THE DRAWING ARE INDICATIVE AND ARE PROVIDED FOR BIDDERS UNDERSTANDING OF SCOPE OF WORK ONLY.ALL DETAILS SHOWN IN THE DRAWING SHALL BE VERIFIED BY CONTRACTOR DURING PRE–ENGINEERING SURVEY & DETAIL ENGINEERING SHALL BE CARRIED OUT BY CONTRACTOR FOR EXECUTION OF WORKS.
* ALL THE DIMENSIONS ARE IN MM AND LEVELS ARE IN METER (U.N.O.)

ISSUED FOR TENDER

REV.	DATE	REVISIONS	BY	CHKD	APPD	PEM/PC
A	01.12.25	ISSUED FOR TENDER	MUNISH	AMS	DP	

इंजीनियर्स इंडिया लिमिटेड ENGINEERS INDIA LIMITED (A Govt. of India Undertaking)

ऑयल एण्ड नेचुरल गैस कारपोरेशन लिमिटेड
OIL AND NATURAL GAS CORPORATION LIMITED

REFURBISHMENT/REPLACEMENT OF BRIDGES IN MH ASSET

STRENGTHENING OF ICW UPPER DECK


SCALE	JOB NO.	UNIT	DIVN.	DEPT.	DWG. NO.	REV.
1:100	B774	101	83	43	0003	A

प्रस्तुत आरेख एवं इसमें निहित डिज़ाइन इंजीनियर्स इंडिया लिमिटेड की संपत्ति है। ये मात्र उधार दिए गए है और न तो इन्हें पुनः मुद्रित किया जाएगा, न नकल की जाएगी, न उधार दिए जाएंगे, न प्रदर्शित किए जाएंगे और न ही संलिप्त और किसी प्रयोग के अलावा इनका कोई अन्य प्रयोग होगा और यह प्रयोग उधार देने वाले द्वारा इंजीनियर्स को लिखित रूप में दी गई सहमति से होगा ।


The drawing, design and details given on this format are the property of ENGINEERS INDIA LIMITED. They are merely loaned on the borrower's express agreement that they will not be reproduced, copied, exhibited or used, except in the limited way permitted by a written consent given by the lender to the borrower for the intended use.

B774-101-83-43-0004


यह ड्राइंग डिज़ाइन एवं इसमें निहित विवरण इंजीनियर्स इंडिया लिमिटेड की संपत्ति है। ये मात्र उधार दिए गए हैं और उधारकर्ता ने यह स्पष्ट समझौता किया है कि न तो इन्हें पुनः तैयार किया जाएगा, न नकल की जाएगी, न उधार दिए जाएंगे, न प्रतिलिपि किए जाएंगे और न ही सार्वजनिक और किसी प्रयोग के अलावा इनका उपयोग इनके मूल अन्य प्रयोग होगा और यह प्रयोग उधार देने वाले द्वारा उधारकर्ता को लिखित रूप में दी गई सहमति से होगा।
The drawing, design and details given on this format are the property of ENGINEERS INDIA LIMITED. They are merely loaned on the borrower's express agreement that they will not be reproduced, copied, exhibited or used, except in the limited way permitted by a written consent given by the lender to the borrower for the intended use.




ELEVATION OF DECK ROW A




PART ELEVATION OF DECK ROW B




PART ELEVATION OF DECK ROW 1




PART ELEVATION OF DECK ROW 3




PART ELEVATION OF DECK ROW 2




SECTION 1–1




SECTION 2–2




SECTION 3–3




SECTION 4–4



SECTION 5–5



SECTION 6–6



SECTION 7–7

REF. DWG. NO.	REFERENCE DRAWING TITLE
ICG-DD-MD-103 TO 108	ICG DECK DRAWINGS

NOTES :-

1. DO NOT SCALE THE DRAWING, WORK TO DIMENSIONS ONLY.
2. ALL DIMENSIONS ARE IN MM AND LEVELS ARE IN M U.N.O.
3. ALL ELEVATIONS ARE W.R.T. CHART DATUM (CD) 0.0M CHART DATUM FOR INDIAN WATERS SHALL BE 2.5M BELOW MEAN SEA LEVEL (MSL).
4. MATERIAL SPECIFICATIONS
   a) ALL STIFFENERS, FLANGE EXTENSION PLATES ETC. SHALL BE OF SAME / HIGHER GRADE AS ELEMENT TO WHICH THEY ARE CONNECTED U.N.O.
5. MATERIAL TYPES LISTED IN SC NOS SHALL CONFORM TO ONGC SPEC 6001 F.
6. FABRICATOR TO ENSURE MIN 75MM CLEAR GAP B/W HE WELDS FOR CROSS BRACES AND CROSS JOINTS.
7. ALL WELDS SHALL BE FULL PENETRATION WELDS.
8. FOR GRATING REFER EIL STD. 7–60–0802.
9. FOR HANDRAIL REFER EIL STD. 7–60–0801.

* ALL DETAILS, DIMENSIONS, LEVELS & MEMBER SIZES IN THE DRAWING ARE INDICATIVE AND ARE PROVIDED FOR BIDDERS UNDERSTANDING OF SCOPE OF WORK ONLY.ALL DETAILS SHOWN IN THE DRAWING SHALL BE VERIFIED BY CONTRACTOR DURING PRE–ENGINEERING SURVEY & DETAIL ENGINEERING SHALL BE CARRIED OUT BY CONTRACTOR FOR EXECUTION OF WORKS.
* ALL THE DIMENSIONS ARE IN MM AND LEVELS ARE IN METER (U.N.O.)

ISSUED FOR TENDER

REV.	DATE	REVISIONS	BY	CHKD	APPD	PEM/PC
A	09.12.25	ISSUED FOR TENDER	MUNISH	AP	DP	

इंजीनियर्स इंडिया लिमिटेड ENGINEERS INDIA LIMITED (A Govt. of India Undertaking)

ऑयल एण्ड नेचुरल गैस कारपोरेशन लिमिटेड
OIL AND NATURAL GAS CORPORATION LIMITED


REFURBISHMENT/REPLACEMENT OF BRIDGES IN MH ASSET

ICG LANDING AREA-MODIFICATIONS


SCALE	JOB NO.	UNIT	DIVN.	DEPT.	DWG. NO.	REV.
1:100	B774	101	83	43	0004	A

3-1641-0501 REV.2 A1-841x594


B774-102-83-43-0004




PART PLAN AT EL(+)25.500 (B.O.S.)




PART PLAN AT EL(+)18.100 (B.O.S.)




PART PLAN AT EL(+)18.100 (T.O.S.)


7800
3000
1000
1700
W16x26
W36x210
W24x62
W36x210
W16
W24x62
2000
W16
W16
W16


B774-102-83-43-0002




PART PLAN AT EL(+)18.500 (T.O.S.)




PART PLAN AT EL(+)18.500 (T.O.S.)




PART PLAN AT EL(+)26.500 (T.O.S.)




SECTION 1–1




PART ELEVATION OF DECK ROW 1




SECTION 2–2




SECTION 3–3



SECTION 4–4



SECTION 5–5



SECTION 6–6

REF. DWG. NO.	REFERENCE DRAWING TITLE
ICP-70-050 TO ICP-70-062	ICP PLATFORM DECK DRAWINGS

NOTES :-

1. DO NOT SCALE THE DRAWING, WORK TO DIMENSIONS ONLY.
2. ALL DIMENSIONS ARE IN MM AND LEVELS ARE IN M U.N.O.
3. ALL ELEVATIONS ARE W.R.T. CHART DATUM (CD) 0.0M CHART DATUM FOR INDIAN WATERS SHALL BE 2.5M BELOW MEAN SEA LEVEL (MSL).
4. MATERIAL SPECIFICATIONS
   a) ALL STIFFENERS, FLANGE EXTENSION PLATES ETC. SHALL BE OF SAME / HIGHER GRADE AS ELEMENT TO WHICH THEY ARE CONNECTED U.N.O.
5. MATERIAL TYPES LISTED IN SC NOS SHALL CONFORM TO ONGC SPEC 6001 F.
6. FABRICATOR TO ENSURE MIN 75MM CLEAR GAP B/W HE WELDS FOR CROSS BRACES AND CROSS JOINTS.
7. ALL WELDS SHALL BE FULL PENETRATION WELDS.
8. FOR GRATING REFER EIL STD. 7-60-0802.
9. FOR HANDRAIL REFER EIL STD. 7-60-0801.

* ALL DETAILS, DIMENSIONS, LEVELS & MEMBER SIZES IN THE DRAWING ARE INDICATIVE AND ARE PROVIDED FOR BIDDERS UNDERSTANDING OF SCOPE OF WORK ONLY.ALL DETAILS SHOWN IN THE DRAWING SHALL BE VERIFIED BY CONTRACTOR DURING PRE-ENGINEERING SURVEY & DETAIL ENGINEERING SHALL BE CARRIED OUT BY CONTRACTOR FOR EXECUTION OF WORKS.
* ALL THE DIMENSIONS ARE IN MM AND LEVELS ARE IN METER (U.N.O.)

ISSUED FOR TENDER

REV.	DATE	REVISIONS	BY	CHKD	APPD	PEM/PC
A	01.12.25	ISSUED FOR TENDER	MUNISH	AP	DP	

इंजीनियर्स इंडिया लिमिटेड ENGINEERS INDIA LIMITED (A Govt. of India Undertaking)

ऑयल एण्ड नेचुरल गैस कारपोरेशन लिमिटेड
OIL AND NATURAL GAS CORPORATION LIMITED

REFURBISHMENT/REPLACEMENT OF BRIDGES IN MH ASSET


ICP LANDING AREA -MODIFICATIONS

SCALE	JOB NO.	UNIT	DIVN.	DEPT.	DWG. NO.	REV.
1:100	B774	102	83	43	0002	A


3-1641-0501 REV.2 A1-841x594

प्रस्तुत आरेख एवं इसमें निहित डिजाइन इंजीनियर्स इंडिया लिमिटेड की संपत्ति है। ये मात्र उधार दिए गए हैं और उधार दिए गए उद्देश्य के अलावा इनका कोई अन्य उपयोग नहीं अन्य प्रयोग होगा और यह प्रयोग उधार देने वाले द्वारा उधारकर्ता को लिखित रूप में दी गई सहमति से होगा।
The drawing, design and details given on this format are the property of ENGINEERS INDIA LIMITED. They are merely loaned on the borrower's express agreement that they will not be reproduced, copied, exhibited or used, except in the limited way permitted by a written consent given by the lender to the borrower for the intended use.


B774-102-83-43-0003




PART ELEVATION OF DECK ROW B




PART ELEVATION OF DECK ROW 3



PART ELEVATION OF DECK ROW 4



PART ELEVATION OF DECK ROW F4



PART ELEVATION OF DECK ROW FB

REF. DWG. NO.	REFERENCE DRAWING TITLE
ICP-70-050 TO ICP-70-062	ICP PLATFORM DECK DRAWINGS

NOTES :-

1. DO NOT SCALE THE DRAWING, WORK TO DIMENSIONS ONLY.
2. ALL DIMENSIONS ARE IN MM AND LEVELS ARE IN M U.N.O.
3. ALL ELEVATIONS ARE W.R.T. CHART DATUM (CD) 0.0M CHART DATUM FOR INDIAN WATERS SHALL BE 2.5M BELOW MEAN SEA LEVEL (MSL).
4. MATERIAL SPECIFICATIONS
   a) ALL STIFFENERS, FLANGE EXTENSION PLATES ETC. SHALL BE OF SAME / HIGHER GRADE AS ELEMENT TO WHICH THEY ARE CONNECTED U.N.O.
5. MATERIAL TYPES LISTED IN SC NOS SHALL CONFORM TO ONGC SPEC 6001 F.
6. FABRICATOR TO ENSURE MIN 75MM CLEAR GAP B/W HE WELDS FOR CROSS BRACES AND CROSS JOINTS.
7. ALL WELDS SHALL BE FULL PENETRATION WELDS.
8. FOR GRATING REFER EIL STD. 7-60-0802.
9. FOR HANDRAIL REFER EIL STD. 7-60-0801.

* ALL DETAILS, DIMENSIONS, LEVELS & MEMBER SIZES IN THE DRAWING ARE INDICATIVE AND ARE PROVIDED FOR BIDDERS UNDERSTANDING OF SCOPE OF WORK ONLY.ALL DETAILS SHOWN IN THE DRAWING SHALL BE VERIFIED BY CONTRACTOR DURING PRE-ENGINEERING SURVEY & DETAIL ENGINEERING SHALL BE CARRIED OUT BY CONTRACTOR FOR EXECUTION OF WORKS.
* ALL THE DIMENSIONS ARE IN MM AND LEVELS ARE IN METER (U.N.O.)

ISSUED FOR TENDER

REV.	DATE	REVISIONS	BY	CHKD	APPD	PEM/PC
A	01.12.25	ISSUED FOR TENDER	MUNISH	AP	DP	

ENGINEERS INDIA LIMITED (A Govt. of India Undertaking)

ऑयल एण्ड नेचुरल गैस कारपोरेशन लिमिटेड
OIL AND NATURAL GAS CORPORATION LIMITED

REFURBISHMENT/REPLACEMENT OF BRIDGES IN MH ASSET

ICP LANDING AREA- MODIFICATIONS

SCALE	JOB NO.	UNIT	DIVN.	DEPT.	DWG. NO.	REV.
1:125	B774	102	83	43	0003	A

3-1641-0501 REV.2 A1-841x594

प्रस्तुत आरेख एवं इसमें निहित डिज़ाइन इंजीनियर्स इंडिया लिमिटेड की संपत्ति है कि न तो उन्हें पुनः मुद्रित किया जाएगा, न नकल की जाएगी, न उधार दिए गए हैं और उधारकर्ता ने यह स्पष्ट समझौता किया है कि न तो उन्हें पुनः मुद्रित किया जाएगा, न नकल की जाएगी, न उधार दिए जाएंगे, न प्रयोग किए जाएंगे और न ही सीमित और किसी प्रयोग के अलावा इसका कोई अन्य प्रयोग होगा और यह प्रयोग उधार देने वाले द्वारा उधारकर्ता को लिखित रूप में दी गई सहमति से होगा ।

The drawing, design and details given on this format are the property of ENGINEERS INDIA LIMITED. They are merely loaned on the borrower's express agreement that they will not be reproduced, copied, exhibited or used, except in the limited way permitted by a written consent given by the lender to the borrower for the intended use.