Addendum to Structure Scope of Work

Following strengthening measures are to be carried out before installation of new bridges:

Sl. No.	Platform Name	Strengthening Required
1	ICG	One member (660 X 12.7 mm) at Jacket walkway level (El +6.96 m) along Row B between Rows 2 and 3 (15m Length) shall be strengthened with 10 mm thick wrap plate (4 Quarters) through the entire length of 15m.
2	ICP	One member (762 X 16 mm) at Jacket walkway level (El +7.8 m) along Row 1 between Rows A and B (13.5m Length) shall be strengthened with 12 mm thick wrap plate (4 Quarters) through the entire length of 13.5m.
3	BHS	One plan brace member (457 X 12.7 mm) at Jacket walkway level (El +6.272 m) supporting the fire water caissons near Leg B1 (3 m Length portion near to fire water caisson supports only) shall be strengthened with 10mm thick wrap plate (4 Quarters).